

Quotation To:	Mr. Masroor	Quote No:		
	Dubai, UAE	Date:		
		Payment Terms:		
Scope of Work	Quotation for Interior decoration and renovation job			
Area	Description of job	Unit	Unit Rate	Total Cost
Kitchen	Kitchen Window Glass Panel (4Nos - 2 Fixed frame & middle two door glass panel & it shall reflect one side view only) Size: W2100 & 1500			
	Kitchen Vinyl Wrapping for entire cabinets doors & drawers (White & Blue combination) with three-year warranty that includes waterproof & heatproof			
	Kitchen cabinet repair and installation of new cabinet door (2Nos) over refrigerator 18mm MDF material			
	Behind Kitchen cabinet inside the store room to install 60CM to 70CM(H) wardrobe with one shelf and two doors of each wardrobes			
	Supply & Install new white marble top with ALL fittings and finishing (Optional as per owner recommendation)			
	Supply & Installation of Kitchen Sink that includes all plumbing fittings & hand spray as to clean the utensils with existing marble space			
	subtotal			
Entire Unit SPC Flooring	SPC Flooring (Waterproof) HJ 8836 with F-Profile 4Nos for the entire 2BR apartment that includes living room, bedrooms & kitchen area (total 135 sq meter). If anything increases or decreases the area will pay back / charge accordingly. (5 Years Warranty except for malfunction or misuse by end-user).			
	F- Profile (Waterproof) HJ 8836 4Nos - If anything increases or decreases the end profile will pay back / charge accordingly. (5 Years Warranty except for malfunction or misuse by end-user).			
Bathroom 1	Demolishing of entire washroom floor & wall tiles including the bathtub and cart away to DM yard cost included			
	Floor preparation and waterproofing works (5-year warranty) for the floor and wall up to 1.2Mtr high as per DM standard.			
	Supply & Installation of floor (Antislipery) & wall tiles (60x60) that gives the marble finish (Color will get approved by client)			
	Supply & Install wall mounted WC (RAK) with wall in-build siphon set that includes waste line relocation and installing the new shattaf (Grohe)			
	Supply & Install Vanity counter top wall mounted with wash basin (RAK or equivalent)			
	Supply & Install Mirror with in-build LED light			
	Supply & Install fixed glass with steel panel & door for standing shower tray			
	Supply & Install shower head with mutiple options (high quality)			
	Supply & Install floor trap & shower tray drain outlet			
	Supply & Install Gypsum ceiling with access panel (60x60) for AC servicing			
	Supply & installation of door threshold			
	Supply & installation of spot lights that includes re-wiring the existing system			
Door with archive trave (front & Back) to paint with white color				
Bathroom 2	Demolishing of entire washroom floor & wall tiles including the bathtub and cart away to DM yard cost included			
	Floor preparation and waterproofing works (5-year warranty) for the floor and wall up to 1.2Mtr high as per DM standard.			
	Supply & Installation of floor (Antislipery) & wall tiles (60x60) that gives the marble finish (Color will get approved by client)			
	Supply & Install wall mounted WC (RAK) with wall in-build siphon set that includes waste line relocation and installing the new shattaf (Grohe)			
	Supply & Install Vanity counter top wall mounted with wash basin (RAK or equivalent)			
	Supply & Install Mirror with in-build LED light			
	Supply & Install fixed glass panel & door for standing shower tray			
	Supply & Install shower head with mutiple options (high quality)			
	Supply & Install floor trap & shower tray drain outlet			
	Supply & Install Gypsum ceiling with access panel (60x60) for AC servicing			
	Supply & installation of door threshold			
	Supply & installation of spot lights that includes re-wiring the existing system			
Door with archive trave (front & Back) to paint with white color				

Guest Bathroom	Demolishing of entire washroom floor & wall tiles & cart away to DM yard cost included			
	Floor preparation and waterproofing works (5-year warranty) for the floor and wall up to 1.2Mtr high as per DM standard.			
	Supply & Installation of floor (Antislipery) & wall tiles (60x60) that gives the marble finish (Color will get approved by client)			
	Supply & Install wall mounted WC (RAK) with wall in-built siphon set that includes waste line relocation and installing the new shattaf (Grohe)			
	Supply & Install Vanity counter top wall mounted with wash basin (RAK or equivalent)			
	Supply & Install Mirror with in-built LED light			
	Supply & Install Gypsum ceiling with access panel (60x60) for AC servicing			
	Supply & installation of door threshold			
	Supply & installation of spot lights that includes re-wiring the existing system			
Door with archive trave (front & Back) to paint with white color				
Majlis Room	Gypsum Open door - Modification of rectangle access to convert into the decorative arch and expand the door width of 30cm and finishing work			
Living room	Supply & Installation of PVC wall cladding with side & wall mounted drawers including LED lights strip / spot lights as specify the client theme concept			
Master Bedroom	Supply & Installation of PVC wall cladding with side & wall mounted drawers including LED lights strip / spot lights as specify the client theme concept			
	Supply & Installation of decorative wooden / PVC strip and wall-mounted mirror next to the washroom available space (As per client theme concept)			
BR 1 & 2 Wardrobe	Supply & apply VINYL'S WHITE WRAPPING for BR 1 & 2 wardrobes as per client recommended color & theme			
Entire 2BR Paint	Supply & apply Jotun Phenomastic Paint with primer and two coat paint with all wall cracks repair work and finishing the wall surface (White color)			
Entire 2BR Door Paint	Supply & apply wooden door white paint with putty work for inside & outside panels that includes the door & frame (archive-tray repair works)			
Main Entrance Side wall	Supply & Installation of SHOE RACK (slim trim to match design concept) & install round mirror with in-built LED light			
Total Amount				